



NOTES

- PRODUCT MANUFACTURED IN ACCORDANCE WITH CSA A23.4
- MINIMUM CONCRETE STRENGTH AT 28 DAYS: 32 MPA
- MAX WATER CEMENT RATIO OF 0.45 & AIR CONTENT OF 5-8%
- HARD STEEL FINISH

BOTTOM 749 kg [1652 lbs]
 LID 451 kg [994 lbs]
 TOTAL 1200 kg [2646 lbs]

WWW.FRASERWAYPREKAST.COM

(604) 534-2911



FRASERWAY PREKAST LTD
 A BMGROUP COMPANY

COPPER TRIUNE VAULT #10778

SIZE A DRAWING #

REV SHEET

TV-C

1/1