



- PRODUCT TO BE MANUFACTURED IN ACCORDANCE WITH CSA A23.4
- MINIMUM CONCRETE STRENGTH AT 28 DAYS: 32 MPA
- WWM IN ACCORDANCE TO ASTM A1064

WWW.FRASERWAYPREKAST.COM

(604) 534-2911



**FRASERWAY PREKAST LTD**  
A BMGROUP COMPANY

## DRYWELL Ø750 [30"] X 610 [24"] RISER 32 HOLE PERFORATED

SIZE  
A

DRAWING #

DW750x.6

REV SHEET  
1/1